

2018 TECHNICAL SPECIFICATIONS
UPDATES
Summary of Changes

S-511 STORM SEWERS

Revisions in this reflect removing SCA-5 bedding material and referencing Standard Detail Sheet D-302.

1. Revised C. to: **The trench shall be backfilled per Standard Detail D-302. All pipes shall be backfilled per Standard Detail D-302 Table 1, unless otherwise shown on the plans. Minimum cover of soil over the top of the pipe shall be 2 feet.**
2. Revised D. to: **Bedding material shall be pared or molded to give full support to each pipe as shown in the Standard Details. Notches shall be cut to receive the bell (when bell and spigot pipe is used).**

S-803 PERMANENT SIGNING

Revisions in this section reflect requiring new signs should they be disturbed as part of a project.

1. Revised A.7. to: **The Contractor shall maintain all existing signs within the project limits that are not to be disturbed and are to remain, whether they're shown on the plans or not. Any sign that is disturbed as part of the project shall be replaced with a new sign. Resetting existing signs is prohibited. At the onset of the project, the Contractor should verify and document the condition of each sign that is to remain in place. The Contractor shall be responsible for the appropriate care of all existing signs that are to remain in place throughout the duration of the project.**
2. Deleted A.10. in its entirety.
3. Added the following to the end of section A.6.: **The contractor shall provide and install the sign posts for these City installed street name signs.**

S-903 PEDESTRIAN BRIDGE

1. Revised A.2 to: **The bridge(s) shall be capable of supporting a 100 pound per square foot uniform live load, or a 10,000 pound vehicle load, whichever produces the greatest stress in the bridge members.**