

60"

Road Improvements 2018

48"



NOTES:

1. SIGN SHALL BE MOUNTED ON TWO 4"x6" POSTS, #1 GRADE LUMBER.
2. SIGN SHALL BE CONSTRUCTED OF 3/4" EXTERIOR A-C PLYWOOD.
3. SIGN AND POSTS SHALL BE PAINTED WITH 2 COATS OF WHITE EXTERIOR PAINT.
4. SIGN SHALL BE ERECTED PRIOR TO ANY CONSTRUCTION ACTIVITY AND MAINTAINED BY THE CONTRACTOR THROUGHOUT CONSTRUCTION. SIGN WILL BE REMOVED UPON PROJECT COMPLETION BY THE CITY.
5. THE SIGN(S) SHALL BE PLACED ON EACH END OF THE PROJECT LIMITS. LOCATION TO BE DETERMINED BY THE ENGINEER.
6. SIGN SHALL BE FASTENED TO POSTS WITH 1/2" BOLTS, NUTS, AND WASHERS PLACED AT 1' CENTERS ON THE POSTS. BACKFILL AROUND POSTS SHALL BE THOROUGHLY TAMPED .
7. SIGN GRAPHICS AND LOGO WILL BE PROVIDED BY THE CITY TO THE CONTRACTOR.
8. ON FEDERALLY FUNDED PROJECTS, SIGN SHALL BE A NON-PARTICIPATING ITEM.
9. GRAPHICS AND SIGN LAYOUT SHALL BE SUBMITTED TO THE CITY FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.
10. IN SITUATIONS WHEN THE SIGN MUST STRADDLE THE SIDEWALK, THE BOTTOM OF THE SIGN SHALL BE 8 FEET ABOVE THE TOP OF THE SIDEWALK. ADDITIONALLY, THE SIGN POSTS SHALL BE LOCATED AT LEAST ONE FOOT FROM THE EDGE OF THE SIDEWALK TO THE SIGN POSTS.
11. TEXT SHALL BE FUTURE STD. (EXTRA BOLD).

www.lenexa.com 2017

| | | |
|---------------------|-------|---|
| REVISED DATE: | 08/17 | <p style="font-size: small;">Lenexa K A N S A S</p> |
| DETAILED: | BKC | |
| APPROVED: | --- | |
| PROJECT SIGN DETAIL | | SHEET D-906 |